



2019 PAPA Regional District 8-0 Highlights

2018 Percent Within Tolerance (PWT)

	District 8 - PWT SUMMARY		
Year	2016	2017	2018
Number of PWT Projects Let	45	55	55
Number HOLA	1	0	0
Number LTS	44	55	55
Average Pay Factors (%)			
Asphalt Content	101.17	98.15	99.74
Primary Control Sieve	100.94	100.41	99.90
#200 Sieve	98.87	99.57	100.26
Density (Cores)	97.75	100.74	101.91
Average Density	93.7	94.1	94.8
Average Overall Lot Pay Factor (%)	0.99	1.00	1.01
Incentive (\$)	\$214,244.95	\$289,497.84	\$575,493.58
Disincentive (\$)	-\$250,310.15	-\$415,485.16	-\$386,689.82

2018 Tons Shipped

Total Production 910,534 tons

866,051 tons RAP/RAS

44,483 tons virgin

636,497 tons WMA

274,037 tons HMA

> 2018 WMA

636,497 total

412,799 tons Construction

223,698 tons Maintenance

> 2018 HMA

274,037 total

202,534 tons Construction

71503 tons Maintenance

▶ Bituminous Designs 2018

Total designs submitted 928

Number of designs used 331

Percentage of designs used 36%

Low producer 8%

High producer 75%

▶ Late Season Paving

7 Projects

7 Different contractors

3 Different Counties

▶ Pilot for Maintenance for 2019

19mm wearing mix

2 ½" minimum compacted

Appropriate SRL designation

35-49% passing #8 screen

All producers were notified of our intent

Reduce the need to seal coat within the year



Questions